

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 17 Twp. 8 Rge. 25 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C E 1/2 NE SE

Lease Owner Empire Drilling Co.

Lease Name Madden Davis Well No. B-1

Office Address Wichita, Kansas 650 4th Natl. Bank Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed December 11 1963

Application for plugging filed December 28 1965

Application for plugging approved December 28 1965

Plugging commenced Jan. 31 1966


Plugging completed Feb. 2 1966

Reason for abandonment of well or producing formation \_\_\_\_\_

Lack of oil

If a producing well is abandoned, date of last production January 4 1966

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Nichols

Producing formation Lansing Kansas City Depth to top 3631 Bottom 3805 Total Depth of Well 3805 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface - Sand	0	224	8 5/8"	199'	-0-
Lansing Kansas City	Lime			5 1/2"	3797'	1147.50

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3805 feet to surface feet for each plug set.

Sanded up to 3645' dump 5 sacks of cement on bottom.

Pulled pipe out of hole pump 20 sacks of mud & 100 sacks of cement in hole.  
Well completed.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1966

CONSERVATION DIVISION  
Wichita, Kansas

2/28/66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.

Address P.O. Box 313 Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Theodore Gore

(~~employee of owner~~) (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.


(Signature)

Theodore Gore  
650 4th Natl. Bank Bldg., Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of February, 19 66

My commission expires September 14, 1966

Sandra Kay Peer  
Sandra Kay Peer  
Notary Public.



WELL LOG

15-065-00447 - 00-00

COMPANY	EMPIRE DRILLING COMPANY
CONTRACTOR	EMPIRE DRILLING COMPANY
FARM	MADDEN DAVIS 'B' # 1
LOCATION	C E/2 NE SE 17-8-25W GRAHAM COUNTY, KANSAS
COMMENCED	12-2-53
COMPLETED	12-11-53

0	TO	40	SAND AND SURFACE CLAY
40	TO	224	SURFACE HOLE
224	TO	2045	SHALE AND SHELLS
2045	TO	2078	ANHYDRITE
2078	TO	3470	SHALE AND SHELLS
3470	TO	3770	SHALE AND LIME
3770	TO	3805	LIME
3805			R.T.D.

XX

SET 199' OF 8 5/8" SURFACE CASING, CEMENTED WITH 125 SACKS OF CEMENT  
ELEVATION: 2346 D. F.

TOPS: ANHYDRITE 2045'; HEEBNER 3595'; TORONTO 3617'; L KC 3631; RTD 3805'

- D.S.T. # 1 = 3700' TO 3707'
- # 2 = 3734' TO 3750'
- # 3 = 3761' TO 3770'
- # 4 = 3777' TO 3805'

SET 3797' OF 5 1/2" CASING, CEMENTED WITH 75 SACKS OF CEMENT

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 29 1965 12/29/65

CONSERVATION DIVISION  
Wichita, Kansas