

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

15-065-02856-0002
API NUMBER None-Completed
4-30-54
LEASE NAME Madden-Davis "A"
WELL NUMBER 2
SPOT LOCATION SE NE NE
SEC. 17 TWP. 8S RGE. 25 EXR(W)
COUNTY Graham

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Petroleum Management, Inc.
ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208
PHONE #(316) 686-7287 OPERATORS LICENSE NO. 5242

DATE WELL COMPLETED 4-30-54
PLUGGING COMMENCED 10-24-83
PLUGGING COMPLETED 11-10-83

CHARACTER OF WELL Oil
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? District #6 - Carl Goodrow

IS ACO-1 FILED? None IF NOT, IS WELL LOG ATTACHED? Lease purchased in 1970; log was not forwarded by previous operator.

PRODUCING FORMATION Kansas City DEPTH TO TOP 3714 BOTTOM 3899 I.D. 3909

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	Oil	3714	3899	7"	3908	11-3-83
						< 530 ft.

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Ran tubing to perforation. Pumped in 25 sacks 50/50 poz., 6% gel, 3% C.C., 2 sacks hulls in 5 sacks gel, 25 sacks cement. Wait 1 hour and pump in another 100 sacks. Pull 500' 7" tubing and pumped in 25 sacks gel, 5 hulls, 100 cement, 5 gel, 70 sacks 50/50 pozmix.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Barlow Well Service LICENSE No. 6690
ADDRESS Box 868
Great Bend, KS 67530

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Dale Silcott (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Dale Silcott
(ADDRESS) 400 N. Woodlawn, #201
Wichita, KS 67208

SUBSCRIBED AND SWORN TO BEFORE ME THIS 21 DAY OF Nov., 19 83



Bonnie Brown
NOTARY PUBLIC

COMMISSION EXPIRES: _____

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 1983
FORM CP-4
REVISED 06-83
CONSERVATION DIVISION
Wichita, Kansas
11/28/83