


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-02248-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

GRAHAM County. Sec. 25 Twp. 8 Rge. (E) 25 (W)
Location as "NE/CNW/SW" or footage from lines SE NE NW
Lease Owner EMPIRE DRILLING COMPANY
Lease Name SCHAMBERGER Well No. 1
Office Address 650 FOURTH NATIONAL BANK BUILDING
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed FEBRUARY 13, 1958 19
Application for plugging filed FEBRUARY 13, 1958 19
Application for plugging approved FEBRUARY 13, 1958 19
Plugging commenced FEBRUARY 13, 1958 19
Plugging completed FEBRUARY 13, 1958 19
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE		0	153	8 5/8"	153	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
BOTTOM PLUG @ 600' CEMENTED WITH 25 SACKS CEMENT THROUGH PIPE
PLUG @ 150' CEMENTED WITH 15 SACKS CEMENT
PLUG @ 40' CEMENTED WITH 10 SACKS CEMENT TO SURFACE OF GROUND.

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1958

CONSERVATION DIVISION
Wichita, Kansas


2/20/58

Name of Plugging Contractor ~~EMPIRE DRILLING COMPANY~~ EMPIRE DRILLING COMPANY
Address 650 FOURTH NATIONAL BANK BUILDING

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, DAN J. KORNFELD (employee of owner) of (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Dan J. Kornfeld*
650 FOURTH NATIONAL BANK BUILDING
(Address)

SUBSCRIBED AND SWORN to before me this 17TH day of FEBRUARY, 1958
My commission expires JULY 2, 1958
Hazel Pierson
Notary Public.



PLUGGING
25-8-25W
FILE SEC. 22731894
BOOK PAGE 76 LINE 7
83-72

15-065-02268-00-00

LLO 6

COMPANY: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
 CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
 FARM: SCHAMBERGER # 1
 LOCATION: SE NE NW SECTION 25-8-25 GRAHAM COUNTY, KANSAS
 COMMENCED: FEBRUARY 5, 1958 ELEVATION: 2372 KB
 COMPLETED: FEBRUARY 13, 1958

0	TO	167	SAND, SHALE
167	TO	1200	SHALE AND CLAY
1200	TO	1575	SHALE AND SHELLS
1575	TO	2091	SHALE AND SAND
2091	TO	2122	ANHYDRITE
2122	TO	2815	SHALE AND SHELLS
2815	TO	3040	SHALE AND LIME
3040	TO	3740	LIME AND SHALE
3740	TO	3880	LIME
		3880	RTD
			D & A

SET: 8 5/8" 153' WITH 115 SACKS CEMENT

TOPS: HEEBNER 3662
 TORONTO 3684
 LANSING KANSAS CITY 3702

FEB 18 1958
 2/18/58

CERTIFICATION

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE SCHAMBERGER NUMBER 1, SE NE NW SECTION 25-8-25, GRAHAM COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 17TH DAY OF FEBRUARY, 1958

Hazel Pierson
 HAZEL PIERSON, NOTARY PUBLIC

MY COMMISSION EXPIRES JULY 2, 1958



FILE SEC 25T. 8 (254)
 BOOK PAGE 83 11. 42