


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-00007-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
518 North Market, Insurance Bldg.
Wichita, Kansas

Russell County, Sec 26 Twp 8 Rgn 25 (E) W (W)
Location as "NE/CNWSWK" or footage from lines SW/4 SE/4 SE/4
Lease Owner Empire Drilling Co
Lease Name Empire Drilling Co-Minium Well No. B1
Office Address Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19 _____
Application for plugging filed _____ 19 _____
Application for plugging approved _____ 19 _____
Plugging commenced _____ Jan 1 _____ 19 62
Plugging completed _____ Jan 13 _____ 19 62
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section First

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4022 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4022 feet to surface feet for each plug set.
Well had been plugged back to XHXX 3997, and casing preforated at 3979. Hole filled with same to 3970, and four sacks of cement placed in bottom of hole with dump bailer; pipe shot off at 2019 and pulled to 500 ft; Hole circulated with mud followed by 20 sacks of cement pumped down to 500 feet, and pipe pulled to 180 ft, and 20 sacks of cement pumped down to 180 ft, and remainder of pipe pulled and hole capped with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1962

CONSERVATION DIVISION
Wichita, Kansas

1/26/62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnes and Sons Pipe Pulling Co
Address Russell, Kansas.

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Irwin Kornfeld (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Irwin Kornfeld
650-4th Nat'l. Bank Bldg., Wichita 2, Kansas
(Address)

Subscribed and Sworn to before me this 25th day of January, 19 62



October 21, 1962
Lucille H. Harr, Notary Public.

15-065-00007-08-00

LOG

COMPANY: Empire Drilling Company, Simon Lebow Corporation
 CONTRACTOR: Empire Drilling Company
 FARM: Minium "B" # 1
 LOCATION: SW SE SE of Section 26-8S-25W, Graham County, Kansas
 COMMENCED: December 8, 1961 ELEVATION: 2483 KB
 COMPLETED: December 20, 1961 POTENTIAL: D # A

0	to	158	Surface Shale
158	to	745	Shale
745	to	1540	Shale-Shells
1540	to	1725	Shale-Shells-Pyrite
1725	to	2135	Shale-Shells
2135	to	2150	Shale
2150	to	2210	Shale-Shells
2210	to	2247	Anhydrite
2247	to	2295	Shale-Shells
2295	to	2460	Lime-Shells
2460	to	2700	Shale-Shells
2700	to	2775	Lime-Shells
2775	to	2807	Shale
2807	to	3375	Shale-Lime
3375	to	3455	Lime
3455	to	3839	Lime-Shale
3839	to	4022	Lime
4022			Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1962

CONSERVATION DIVISION
Wichita, Kansas

9/24/62


SET: 142' of 8 5/8" casing with 100 sacks cement.
 4017' of 5 1/2" casing with 75 sacks cement.

SAMPLE TOPS:

Anhydrite	2210	+ 273
Heebner	3781	-1298
Toronto	3805	-1322
Lansing	3821	-1338
Rotary Total Depth	4022	

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Minium "B" # 1, SW SE SE of Section 26-8S-25W, Graham County, Kansas as reflected by the files of Empire Drilling Company.


 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 29th day of December, 1961.


 Lucille H. Harr, Notary Public

My Commission expires October 21, 1962.