


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-065-20148-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 26 Twp. 8S Rge. (E) 25 (W)

Location as "NE/CNW/SW" or footage from lines 150' N of C SE SE

Lease Owner Chief Drilling Co., Inc.

Lease Name MINIUM Well No. 2

Office Address Box 797 - Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 6/2, 19 68.

Application for plugging filed 6/9, 19 68

Application for plugging approved 6/9, 19 68

Plugging commenced 6/9, 19 68

Plugging completed 6/9, 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols - Morland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4063 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	227'	8-5/8"	227'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set 980' to 1300'  
Mixed 100 sacks cement through drill pipe  
Wooden plug set 980' to 240'  
Mixed 18 sacks cement through drill pipe  
Wooden plug set 240' to 180'  
Mixed 20 sacks cement through drill pipe  
Wooden plug set 180' to 40'  
Mixed 3 sacks cement through drill pipe  
Mixed 10 sacks cement from 40' to cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas

6/11/68

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor  
Address

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Jim Robinson, Office Mgr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson  
Box 797 - Great Bend, Kansas 67530  
(Address)

Subscribed and Sworn to before me this 10th day of June 19 68

Dec. 12, 1970  
Carmen R. Cook, Notary Public.



15-065-20148-00-00

WELL LOG

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas

6/11/68

Chief Drilling Co., Inc.  
Box 797  
Great Bend, Kansas 67530

MINIUM #2  
150' N of C SE SE  
Section 26-8S-25W  
Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 5-27-68  
Completed: 6-2-68

Casing Record: 8-5/8" set @ 227' w/150 sacks Pozmix, 2% Gel.

TEMPORARILY ABANDONED

FORMATION	FROM	TO	ELEVATION	
Shale	0	100	2474 Gr.	
Shale & Sand Streaks	100	227	2476 D.F.	
Shale	227	1075	2479 K.B.	
Sand Streaks & Shale	1075	1400		
Shale & Sand	1400	2210		
Anhydrite	2210	2244		
Shale & Shells	2244	2585		
Shale & Lime	2585	3830		
Lime	3830	4060		
Total Depth	4060			
			FORMATION TOPS	
			SAMPLE	LOG TOPS
		Anhydrite	2210	
		Heebner	3781	3785 -1306
		Toronto	3806	3810 -1331
		Lansing	3822	3827 -1348
		Base K.C.		4045 -1566
		Total Depth	4060	4063 -1584

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled 150' N of C SE SE Section 26-8S-25W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF-DRILLING-CO., INC.

*Thomas G. Wesselowski*  
Thomas G. Wesselowski

Subscribed and sworn to before me this 3rd day of June, 1968.

*Carmen R. Cook*  
Carmen R. Cook, Notary Public

My commission expires: Dec. 12, 1970.

