

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20145-00-00

RECEIVED 6-3-68
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Helberg Oil Company,

Complete Address: Morland, Kansas.

Lease Name Helberg Well No. 3

Location CNE-SE Sec. 19 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 4025'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 11:30AM Day 28 Month 5 Year 1968

The Above well was plugged as follows:

1131--8 5/8" Surface pipe, cement circulated with 100 Sx.
Dakota Section top @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru
DP from 1300' to 975'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from
180' to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dehals
Well Plugging Supervisor

DATE 6/4/68
INV. NO. 4873-W