

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-30179-00-00

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1966

9-30-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Helberg Oil Company.

Complete Address: Morland, Kansas.

Lease Name Helberg Well No. 1

Location SW-NE-NW Sec. 19 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3863

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 12:00 Day 25 Month 9 Year 1966

The Above well was plugged as follows:

112'--8 5/8" Surface pipe, cement circulated with 75 Sx.

Circulated hole with heavy mud, set plug @ 400' and displaced 15 Sx.

cement thru DP. Heavy mud to 200', set plug with 1/2 sack hulls and

displaced 15 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2

sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 9/30/66  
INV. NO. 4023-w