

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

13-065-30283-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1967  
6-26-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Helberg Oil Company,

Complete Address: Morland, Kansas.

Lease Name Marion C. Helberg Well No. 2

Location SW-SW-SE Sec. 19m Twp. 8 Rge. (E) (W)25

County Graham Total Depth 1070'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated: Lost hole

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 10:15AM Day 16 Month 6 Year 1967

The Above well was plugged as follows:

This well was started as an anhydrite test. No surface pipe was set. 7 7/8" hole from bottom of cellar to TD. Hole was lost due to pipe slip having been dropped in hole.

Pushed plug to 500' and displaced 20 Sx. cement thru DP. Filled hole with heavy mud to 150', set plug with 1/2 sack hulls and filled hole to bottom of cellar with 50 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. R. D. Dibel  
Well Plugging Supervisor

DATE 6/27/67  
INV. NO. 5455-W