

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-02791-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1966
3-28-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name McAdams Pipe and Supply Company,

Complete Address: Box # 295, Great Bend, Kansas.

Lease Name A. Schmeid Well No. 1

Location CNE-NE Sec. 20 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3886

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Incorporated,

Address: Box #486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 9:00AM Day 24 Month 3 Year 1966

The Above well was plugged as follows:

204'--8 5/8" Surface pipe, cement circulated with 125 Sx.
3884'--5 1/2" ~~XXXXXXXX~~ Production casing cemented with 125 Sx. Well plugged
back to 3853'. Top perforations from 3828' to 3853'.

Sanded well back to 3815' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing to 600' and circulated heavy gel mud. (Used 20 Sx. gel).
Pulled 5 1/2" to 540' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to
195' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge
@ 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: K. L. Nichols
Well Plugging Supervisor

DATE 3/28/66
INV. NO. 2950-44