

KANSAS

*JL*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20393-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas 11-30-70

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Culley Well No. 1

Location NE-NE-SW Sec. 20 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3752'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.     

Operation Completed: Hour 12:00 M Day 22 Month 11 Year 1970

The above well was plugged as follows:

189'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 100 Sx. cement thru  
DP from 1400' to 1075'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 12/1/70  
INV. NO. 8966-4