

15-065 · 00281 - 00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 52-16

LOCATION NW NW SE

SEC. 21 TWP. 8 RGE. 25W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. A-1 Lease _____ Schmeid. "A"

Operator Tennessee Gas Trans Address Box 163 Great Bend, Kans

Field _____ County Graham

Total Depth 3950 Feet.

Plugging Contractor R & S Pipe Pulling and Globe Cementing Co

Plugging Contractor's License No. 1

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 265' circulated with cement - 5 1/2" 3948' with 125 sax

cement behind - P.B. to 3902' perforations at 3740'

Filled with sand to 3725', set 4 sax cement with dump bailer, pulled

5 1/2" to 1000', circulated hole with heavy mud (Gel), displaced 25 sax

cement through 5 1/2" at 600', heavy mud to 260', displaced 15 sax cement

through 5 1/2", heavy mud to 35', set rock and 10 sax cement to bottom

cellar.

Mudding and Cementing by Globe Cementing.

Leon Petty

District Conservation Agent

Date 10-25-57

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1957
10/28/57
CONSERVATION DIVISION
Wichita, Kansas

3
2118 R 250
BOOK PAGE 52 LINE 16