

15-045-01348-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
11/8/68 NOV 8 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Ivy Oil Company,

Complete Address: Box #86, Plainville, Kansas.

Lease Name Adelia Schmeid Well No. 1-C

Location NE-NE-NW Sec. 21 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3856

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 12:30PM Day 6 Month 11 Year 1968

The Above well was plugged as follows:

199'--8 5/8" Surface casing, cement circulated with 150 Sx.
3855'--4 1/2" Production casing cemented on bottom with 125 Sx. Well Plugged back to
3811'. Top perforations @ 3701'.

Sanded well back to 3650' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well with initially 9 Bbl. heavy drilling mud and followed with 95 Sx.
cement from 1175' to 875', then 39 Bbl. heavy drilling mud from 875' to 225' and
followed with 25 Sx. cement from 225' to 150' then 7 Bbl. heavy drilling mud from
150' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in
pressure-100#. Final shut-in pressure-50#.(Mudding & Cementing by Allied Cementing Co.).

I hereby certify that the above well was plugged as herein stated.

Signed: A. S. Dickel
Well Plugging Supervisor

INVOICED

DATE 11/8/68

INV. NO. 8789-W