

15-045-01358-00-01

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1968
CONSERVATION DIVISION
Wichita, Kansas
11/8/68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ivy Oil Company,

Complete Address: Box #86, Plainville, Kansas.

Lease Name Adelia Schmeid Well No. 3-C

Location NW-NW-NW Sec. 21 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3880'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 1:45 PM Day 6 Month 11 Year 1968

The Above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated with 115 Sx.
3876'--5 1/2" casing cemented on bottom with 125 Sx. Well plugged back to 3850'. Top perforations @ 3718'.

Pushed plug to 3600', built sand bridge and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well with initially 9 Bbl. heavy rotary drilling mud and followed with 95 Sx. cement from 1175' to 875' then 39 Bbl. heavy drilling mud from 875' to 225' and followed with 25 Sx. cement from 225' to 150' then 7 Bbl. heavy drilling mud from 150' to 30' and finally 10 Sx. cement from 30' to bottom of cellar.

Max. pump-in press.-100#. FSIP-50#. (Mudding and cementing by Allied Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INDEXED
DATE 11/8/68
INV. NO. 8791-11

Signed: W. L. D. [Signature]
Well Plugging Supervisor