

15-065-02857-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

6/6/62

JUN 6 1962

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham

Location: SW SW NE Sec. 21 Twp. 8 Rge. _____ (E) _____ (W) 25

Name of Field: _____ Total Depth: 3917

I have this date completed supervision of plugging of:

Lease Name: X Schmied Well No. B-2 D1

Operator's Full Name: Great Bend Pipe & Supply

Complete Address: Drawer (B) Great Bend, Kans

Plugging Contractor Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Oil Well x Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No x

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 30 Month 5 Year 62

The above well was plugged as follows:

8 5/8" 262' circulated with cement - 4 1/2" 3916' with 125 sax cement.

Sand to 3900', set 3 sax cement with dump bailer, pulled 1125' 4 1/2" to

550', circulated hole with heavy mud through 4 1/2" (12 sax Gel), displaced

20 sax cement through 4 1/2" at 550', heavy mud to 170', displaced 20 sax

cement through 4 1/2" at 170', heavy mud to 35', set bridge and filled to

bottom cellar with cement.

Mudding and cementing by Knight Company Pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 6/6/62
INV. NO. 5104-W