

15-065-02858-00-00

KANSAS

Form CP-3  
Rev. 6-26-62

*W*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

*7/3/67*  
JUL 3 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Four Way Operating, Incorporated,

Complete Address: Box # 698, Great Bend, Kansas.

Lease Name Schmeid Well No. A-2

Location SE-NW-SE Sec. 21 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3975'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Pipe Pullers, Incorporated,

Address: Box # 486, Ellinwood, Kansas. License No. 462

Operation Completed: Hour L; 30PM Day 29 Month 6 Year 1967

The Above well was plugged as follows:

300'--8 5/8" Surface pipe, cement circulated with 175 Sx.

3974'--4 1/2" Production casing cemented with 150 Sx. Well plugged back to 3826'. Top perforations @ 3765'.

Pushed plug to 3700', set 10' rock bridge and 4 Sx. cement with dump

bailer. Pulled 4 1/2" casing, squeezed well with 31 sacks gel using 5 sacks

hulls in initial gel, followed with 55 sacks cement then 4 sacks gel

then 10 Sx. cement for cap. Maximum pump-in pressure 200#. FSIP--50#.

(Recovered 900' 4 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Pichel*  
Well Plugging Supervisor

INVOICED  
DATE 7/3/67  
INV. NO. 5503-4