

15-065-20045-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

6/19/67 JUN 19 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Olin Babcock Well No. 1

Location 1320' FEL & 440' FSL--SE Sec. 21 Twp. 8 Rge. (E) (W)25

County Graham Total Depth 3990'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 4:30AM Day 16 Month 6 Year 1967

The Above well was plugged as follows:

250'--8 5/8" Surface pipe, cement circulated with 185 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 270', set plug with 1/4 sk. hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated,

Signed: M. L. Dehler
Well Plugging Supervisor

INVOICED

DATE 6/19/67
INV. NO. 5424-W