

R

15-045-20237-00-00

KANSAS

Form CP-3
Rev. 6-1-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Babcock Well No. 1

Location App.-SW-NE-SW Sec. 21 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3676'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Garvey Drilling Company,

Address Rte. #2, Great Bend, Kansas. License No. _____

Operation Completed: Hour 9:30 PM Day 26 Month 6 Year 1969

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru
DP from 975' to 350'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from 275'
to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED
CONSERVATION DIVISION
Wichita, Kansas

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 7-1-69

INV. NO. 25-W

7/1/69