

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20626-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1973
11-6-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Josaphine Well No. 1

Location NE-NE-SW Sec. 23 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3920'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Ks. License No.

Operation Completed: Hour 3:00 PM Day 2 Month 11 Year 1973

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement
thru DP from 1125' to 800'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru
DP from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED
I hereby certify that the above well was plugged as herein stated.
DATE 11/7/73
INV. NO. 8128-W
Signed: M. L. Dickols
Well Plugging Supervisor