

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

15-065-00211-00-01

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 61-2

LOCATION SW SW SE

SEC. 24 TWP. 8 RGE. 25

reworked dry hole

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Engelman

Operator Jones Shelburne Farmer Address Russell, Kans

Field \_\_\_\_\_ County Graham

Total Depth 4250 Feet.

Plugging Contractor West Supply Co & Halliburton Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 203' circulated with cement - 5 1/2" at 3930' with 125 sax  
cement behind - Lane Wells plugs to 3750', perforated 3734'

Filled with sand to 3690', set 5 sax cement with dump bailer, pulled  
1200' 5 1/2" to 700', circulated hole with heavy mud ( Gel ) through  
5 1/2" - displaced 20 sax cement through 5 1/2" at 700', heavy mud to  
190', displaced 20 sax cement through 5 1/2" at 190', heavy mud to  
35', set rock and 10 sax cement to bottom cellar.

Mudding and Cementing by Halliburton Cementing Co.

*Edward Petty*  
District Conservation Agent

Date 11-27-57

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 4 1957  
CONSERVATION DIVISION  
Wichita, Kansas

12-4-57

**PLUGGING**  
FILE SEC. 24 T. 8 R. 25  
BOOK PAGE 61 LINE 2