

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15065-20329-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1970  
CONSERVATION DIVISION  
Wichita, Kansas

5-19-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Richmeier Well No. E-1

Location CNE-SE Sec. 27 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 4055'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Garvey Drilling Company,

Address Route #2, Great Bend, Kansas. License No.       

Operation Completed: Hour 10:30 PM Day 16 Month 5 Year 1970

The above well was plugged as follows:

219'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1025'.

circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru  
DP from 1250' to 925'. Pulled DP to 250' and displaced 25 Sx. cement thru DP from  
250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/22/70

INV. NO. 1917-4

Signed: M. L. Nichols  
Well Plugging Supervisor