

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20102-00-00

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1967

12-7-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kaiser-Francis,

Complete Address 909 Palace Building, Tulsa, Oklahoma. 74103

Lease Name St. John Well No. B-1

Location NE-NE-SW Sec. 33 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3770

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No. _____

Operation Completed: Hour 1:30PM Day 2 Month 12 Year 1967

The above well was plugged as follows:

210'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1000' to 1175'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 880'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from
210' to 150'. Pulled DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. D. Doherty
Well Plugging Supervisor

DATE 12/7/67

INV. NO. 6860-u