

*JF*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-30018-00-00

RECEIVED  
STATE CORPORATION COMMISSION

MAR 22 1965

3-22-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Kaiser--Francis,  
Complete Address: 909 Palace Building, Tulsa, Oklahoma.  
Lease Name Setchell "A" Well No. 1  
Location NW-NW-NW Sec. 34 Twp. 8 Rge. (E) (W) 25  
County Graham Total Depth 4000  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: Leben Drilling, Incorporated,  
Address: Box # 486, Great Bend, Kansas. License No.       
Operation Completed: Hour 7:00PM Day 18 Month 3 Year 1965

The Above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.  
cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and  
displaced 20 Sx. cement thru DP. Heavy mud to 40', Set plug with  
1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 3/22/65  
INV. NO. 847-11

Signed: M. L. Nichols  
Well Plugging Supervisor