

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20203-00-00

RECEIVED
CORPORATION COMMISSION
FEB 12 1969
CONSERVATION DIVISION
Wichita, Kansas

2-12-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name Richmeier Well No. 1

Location CNE-NE Sec. 35 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 4065'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 8:00PM Day 6 Month 2 Year 1969

The Above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. - Pulled-DP-to-1300' and displaced-100-Sx; cement thru
DP from 1300' to 975'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/12/69

INV. NO. 9316-W