


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County. Sec. 12 Twp. 8S Rge. 24 (W)
Location as "NE/CNW/SE" or footage from lines 560' south of North Line and
330' East of West Line of SE/4 Barnett Oil Company

Lease Name Evans Well No. 1
Office Address 411 First National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 9, 19 58
Application for plugging filed May 9, 19 58
Application for plugging approved May 12, 19 58
Plugging commenced May 9, 19 58
Plugging completed May 9, 19 58
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3787 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	195'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 550'. Set plug with 75 feet of cement on top.
Filled hole to 195' with heavy mud. Set plug with 1/2 sack of hulls and 45 feet of cement on top.
Filled hole to 40' with heavy mud. Set plug with 1/2 sack of hulls on top and filled hole with cement to bottom of cellar.

(Well Log attached)

RECEIVED
STATE CORPORATION COMMISSION

MAY 16 1958
5-16-1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. H. Rousey (employee of ~~operator~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey
411 First National Bank Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of May 19 58
My commission expires February 27, 1960.

Mildred F. Willis
Notary Public.



PLUGGING
FILE SEC 12 T 8 R 24W
BOOK PAGE 99 LINE 26

BARNETT OIL COMPANY
WELL LOG - EVANS NO. 1
 LOCATED 560 FEET SOUTH OF THE NORTH LINE
 AND 330 FEET EAST OF THE WEST LINE
 OF THE SOUTHEAST QUARTER (SE/4) OF
SECTION 12-8S-24W, GRAHAM COUNTY, KANSAS

Date Started: 4-29-58
 Date Plugged: 5-9-58

<u>From</u>	<u>To</u>	<u>Formation</u>
0	35	Surface Clay
35	50	Sand
50	80	Shale
80	95	Sand
95	120	Shale
120	130	Sand
130	280	Blue Shale
280	1040	Shale and Shells
1040	1100	Sand
1100	1375	Shale and Shells
1375	1425	Shale and Sand
1425	1460	Shale and Red Bed
1460	1480	Sand
1480	1500	Shale
1500	1590	Sand
1590	1953	Shale
1953	2005	Anhydrite
2005	3155	Shale and Lime
3155	3330	Lime
3330	3485	Lime and Shale
3485	3787	Lime (Total Depth) (D. & A.)

Set 195' of 8 5/8", 24# s.s. casing
 with 140 sacks of Portland cement.

RECEIVED

STATE OF KANSAS COMMISSION

MAY 16 1958

5-16-1958
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING

FILE SEC 12 T 8 R 24 W
 BOOK PAGE 99 LINE 26