


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 12 Twp. 8 Rge. 24 ~~xxx~~ (W)  
Location as "NE/CNW/SW" or footage from lines NE/4 SW/4 NE/4  
Lease Owner Barnett Oil Company  
Lease Name Evans Well No. 1  
Office Address 411 First Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 14, 1957  
Application for plugging filed February 14, 1957  
Application for plugging approved February 15, 1957  
Plugging commenced February 14, 1957  
Plugging completed February 14, 1957  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3785 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	147 1/2'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 150'. Set plug with 1/2 sack of hulls and 15 sacks of cement; filled hole with mud to 40'; set plug and wired at 40' with 1/2 sack of hulls and 10 sacks of cement; shoved 1/2 sack of hulls 10' in rat hole and cemented with 2 sacks.

(Well Log attached)

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Barnett Drilling, Inc.  
Address 409 First Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
F. H. Rousey (employee of ~~owner~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey  
411 First Nat'l Bank Bldg., Wichita, Kansas  
(Address)



PLUGGING  
FILED SEC 12 T 8 R 24W  
BOOK PAGE 141 LINE 5

Melissa F. Willis  
RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public.


FEB 20 1957  
2-20-1957  
CONSERVATION DIVISION  
Wichita, Kansas

BARNETT OIL COMPANY  
WELL LOG - EVANS WELL NO. 1  
NE/4 SW/4 NE/4 OF SECTION 12-8S-24W  
GRAHAM COUNTY, KANSAS

Date Started: 2/ 6/57  
Date Completed: 2/15/57

<u>From</u>	<u>To</u>	<u>Formation</u>
0	35	Post Rock
35	50	Sand
50	148	Shale
148	950	Shale and shells
950	1260	Sand and shale
1210	1275	Pyrite
1275	1555	Shale and shells
1555	1700	Sand
1700	1952	Shale
1952	1987	Anhydrite
1987	2055	Shale
2055	2295	Shale and shells
2295	2555	Lime and shale
2555	3785	Lime (D. & A.)

Set 147½' of 8 5/8", 24# casing  
with 125 sacks of cement.



**RECEIVED**  
STATE CORPORATION COMMISSION

2-20-1957  
FEB 20 1957

CONSERVATION DIVISION  
Wichita, Kansas