

15-065-01341-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 12 Twp. 8 Rge. 24 (E) (W) X

Location as "NE/CNW/SW" or footage from lines. NW NW NW
Lease Owner Barnett Oil Co.
Lease Name Nicholson Well No. #1
Office Address 411 First National Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 10-28-70 19____
Application for plugging approved _____ 19____
Plugging commenced 11-16-70 19____
Plugging completed 11-24-70 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3823' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3822'	1057.34'
				8 5/8"	122'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3725'. Mixed and ran 5 sacks cement thru dump bailer.
Squeezed hole with 5 sacks hulls - 15 sacks gel, followed with 90 sacks cement. Cement from 1100' to 800', followed with 15 sacks gel. Gel from 800' to 200'. Released plug and displaced with 60 sacks cement. Cement from 200' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1970

CONSERVATION DIVISION
Wichita, Kansas

11-30-1970

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of November, 19 70

Sidney D. Miller
Notary Public.

My commission expires October 1972



BARNETT OIL Co.

10-27-70

Nicholson #1

NW NW NW sec 12-85-~~12~~²⁴W Graham Co.

0-40 Soil & sand.

40-122 Shale & shells.

Set 122' 8⁵/₈ cement 10054x CIRC.

122-1045 shale & shells.

1045-1645 sand.

1645-1740 sand.

1740-1985 shale & shells

1985-2018 Anhydrite.

2018-2280 shale & shells

2280-2570 Shale & lime.

2570-3822 1/2 lime.

Rotary TD 3823

Set 3824' of 5 1/2" 14# casing at 3823
Cemented w/ 1253ax. Plug down
4:30 AM 12-2-49.

Per w/ 47 holes 3741 to 3782.

Plug Back TD 3801.

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1970
CONSERVATION DIVISION
Wichita, Kansas
10-29-1970

Deane D. Sharpe