

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Graham County, Sec. 20 Twp. 8S Rge. 24 ~~xxx~~ (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines A/C NW $\frac{1}{4}$  SE $\frac{1}{4}$  SW $\frac{1}{4}$

Lease Owner Barnett Oil Company

Lease Name Law Well No. 1

Office Address 411 First National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 24, 19 59

Application for plugging filed April 24, 19 59

Application for plugging approved April 27, 19 59

Plugging commenced April 24, 19 59

Plugging completed April 24, 19 59

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3920 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 20 sacks of cement at 600' through drill pipe.  
Filled hole with mud to 205'. Set plug at 205' with 1/2 sack of hulls on top and 20 sacks of cement. Filled hole to 40' with mud. Set plug at 40' and wired with 1/2 sack of hulls on top and 10 sacks of cement.

Plugged rat hole with 2 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 1 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Barnett Drilling, Inc.  
Address 409 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
F. H. Rousey, Office Manager, (employee of ~~owner~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey  
411 First National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 1959  
My commission expires February 27, 1960.  
Mildred F. Willis  
Notary Public.



PLUGGING  
FILE SEC 20 T 8 R 24W  
BOOK PAGE 33 LINE 35

15-065-00825-00-00

BARNETT OIL COMPANY  
WELL LOG - LAW WELL NO. 1  
A/C NW/4 SE/4 SW/4 OF SECTION 20-8S-21W  
GRAHAM COUNTY, KANSAS

<u>From</u>	<u>To</u>	<u>Formation</u>
0	50	Surface Clay
50	60	Sand
60	105	Shale
105	115	Sand
115	208	Shale and shells
208	490	Shale
490	970	Shale and shells
970	1020	Sand
1020	1100	Shale
1100	1365	Sand
1365	1520	Shale and shells
1520	1650	Shale
1650	1850	Sand
1850	2085	Shale
2085	2120	Anhydrite
2120	2345	Shale and shells
2345	2570	Shale and lime
2570	2815	Lime
2815	3390	Lime and shale
3390	3920	Lime (T.D.) (D. & A.)

Set 8 5/8", 28# used casing at 207'  
with 160 sacks of H.A. 5 cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 1 1959  
GENERAL DIVISION  
5-1-59

PLUGGING  
FILE SEC 20 T 8 R 24W  
BOOK PAGE 33 LINE 25