

15-065-20094-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Graham County, Sec. 20 Twp. 8S Rge. 24W (W)

Location as "NE/CNW/SW" or footage from lines C SW NE  
Lease Owner Empire Drilling Co.  
Lease Name Law Well No. 1  
Office Address 650 Fourth Nat'l Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-26-67 19  
Application for plugging filed 11-26-67 19  
Application for plugging approved 11-26-67 19  
Plugging commenced 11-26-67 19  
Plugging completed 11-26-67 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3860 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	208'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug set @ 1050' cemented with 100 sacks cement  
set plug @ 230' cemented with 20 sks. cement  
Bridged plug @ 40' with 1 1/2 sks. hulls, 10 sks. cement

RECEIVED  
STATE CORPORATION COMMISSION

DEC 1 1967

12-1-67

CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
Box 486, Great Bend, Kansas 67530  
(Address)



Subscribed and sworn to before me this 30th day of November, 1967  
Ulanda Nichols  
Notary Public.

DRILLER'S LOG

COMPANY: Empire Drilling Co.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: LAW #1  
 LOCATION: C SW NE SECTION 20-8S-24W  
 GRAHAM COUNTY, KANSAS  
 COMMENCED: 11-18-67  
 COMPLETED: 11-26-67

0	208	Shale, Sand
208	850	Shale
850	1268	Sand, Shale
1268	1608	Shale, Sand
1608	1700	Sand
1700	1978	Redbed
1978	2010	Anhydrite
2010	2177	Redbed, Shale
2177	2540	Shale, Lime
2540	2573	Sand, Shale
2573	2590	Shale, Lime
2590	3000	Lime, Shale
3000	3540	Shale, Lime
3540	3650	Lime, Shale
3650	3686	Lime
3686	3795	Lime
3795	3830	Lime, Shale
<u>3830</u>		<u>RTD - D. &amp; A.</u>

8 5/8" 8 rd. 24# used surface casing set @ 208' cemented with 175 sacks Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Law #1 Well, located C SW NE of Section 20, Township 8 South, Range 24 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

RECEIVED  
 CORPORATION COMMISSION

STATE OF KANSAS )  
 COUNTY OF BARTON )

SS DEC 1 1967  
 12-1-67  
 CONSERVATION DIVISION  
 STATE OF KANSAS

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 30th day of November, 1967.



*Ulanda Nichols*

Ulanda Nichols

My Commission Expires:  
 April 1, 1971