

15-065-00717-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 21 Twp. 8 Rge. 24 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SW
Lease Owner National Cooperative Refinery Association
Lease Name Rutherford Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 5, 1955
Application for plugging filed March 7, 1955
Application for plugging approved March 7, 1955
Plugging commenced March 5, 1955
Plugging completed March 5, 1955
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4206 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	195'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Mudded hole to 190', set plug with 1/2 sax hulls / 15 sax cement. Mudded hole to 40', set plug with 1/2 sax hulls / 10 sax cement on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 1121 Union National Bank Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.R. Sears
305 Rule Building, Wichita, Kansas (Address)


SUBSCRIBED AND SWORN to before me this 8th day of March, 1955

My commission expires June 30, 1958.

C. Orville May Notary Public.

C. Orville May COMMISSION

1955 3-9-55
CONSERVATION DIVISION
Wichita, Kansas



PLUGGING
FILE SEC 21 T 8 R 24 W
BOOK PAGE 101 LINE 43

24-7368-S 3-53-20M

L O G

COMPANY: NATIONAL COOPERATIVE REFINERY ASSOCIATION

CONTRACTOR: EMPIRE DRILLING COMPANY

FARM: RUTHERFORD #1

LOCATION: SW SW SW SEC. 21-8-24 GRAHAM COUNTY, KANSAS

COMMENCED: 2-20-55

COMPLETED: 3-5-55

0	TO	200	SURFACE HOLE
200	TO	1120	SHALE AND SAND
1120	TO	1420	SHALE, SHELLS & SAND
1420	TO	2005	SHALE
2005	TO	2041	ANHYDRITE
2041	TO	2460	SHALE AND SHELLS
2460	TO	3015	SHALE AND LIME
3015	TO	3110	LIME
3110	TO	3355	SHALE AND LIME STREAKS
3355	TO	3420	SHALE AND LIME
3420	TO	3890	LIME
3890	TO	4030	LIME AND SHALE
4030	TO	4074	LIME
4074	TO	4110	LIME AND SHALE STREAKS
4110	TO	4180	SHALE AND LIME
4180	TO	4206	LIME
4206			R.T.D.

SET 195' OF 8 5/8" SURFACE CASING, CEMENTED WITH 115 SACKS OF CEMENT.

ELEVATION: 2318 K.B.

TOPS: ANHYDRITE 2005';

D.S.T. #1 3775' TO 3785'; D.S.T. #2 3812' TO 3830'; D.S.T. #3 3824 TO 3848'

D & A

RECEIVED
SITE SUPERVISOR'S COMMISSION

C E R T I F I C A T I O N

3-11-55

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE RUTHERFORD #1, SW SW SW SECTION 21, TOWNSHIP 8, RANGE 24 WEST, GRAHAM COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 8TH DAY OF MARCH, 1955.

MY COMMISSION EXPIRES DECEMBER 10, 1956

W. Valentini
NOTARY PUBLIC



PLUGGING
FILE SEC 21-8-24
BOOK PAGE 101 LINE 43