


13-065-21231-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 23 Twp. 8S Rge. 24 XXW
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines _____
SE NW SW
Lease Owner Zenith Drilling Corporation
Lease Name GATES Well No. 1
Office Address 505 Fourth Financial Center, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole
Date Well completed _____ May 17 1980
Application for plugging filed (Verbally) _____ May 17 1980
Application for plugging approved (Verbally) _____ May 17 1980
Plugging commenced _____ May 17 1980
Plugging completed _____ May 17 1980
Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production _____
_____ 19____



Locate well correctly on above
Section Plot

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900'
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 3900'.
Set 1st plug at 900' with 60 sacks, 2nd
2nd plug at 240' with 30 sacks,
3rd plug 40' solid bridge with 10 sacks,
and rathole with 5 sacks.
Plug was down at 1:30 a.m., 5-17-80.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. 6-5-80
Jack L. Partridge, Asst. Sec.=Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1980



Sherrie L. Brooks
Notary Public.

My commission expires _____

CONTRACTOR'S WELL LOG

15-005-21231-00-00

OPERATOR: Zenith Drilling Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: GATES #1
 LOCATION: SE NW SW, Section 23-8S-24W
 Graham County, Kansas
 SPUD DATE: 5-12-80
 COMPLETION DATE: 4-17-80

0	244	Clay & Shale
244	910	Shale
910	2032	Shale & Sand
2032	2062	Anhydrite
2062	3283	Shale
3283	3750	Shale & Lime
3750	3900	Lime
	3900	Rotary Total Depth

Spud hole at 1:30 p.m., 5-12-80. Drilled 244' of 12-1/4" hole. Ran 6 joints of 8-5/8" casing. (Tally 234'). Set at 242' R.T.D. Cemented with 190 sacks of common, 3% Ca.Cl., 2% gel. Cement did circ. Cement by Sun Cement. Plug was down at 5:30 p.m., 5-12-80.

T.D. 3900'. Set 1st plug at 900' with 60 sacks, 2nd plug at 240' with 30 sacks, 3rd plug 40' solid bridge with 10 sacks, and rathole with 5 sacks. Plug was down at 1:30 a.m., 5-17-80.

SAMPLE TOPS:

Anhydrite 2032'
 B/Anhydrite 2062'

RECEIVED
 STATE CORPORATE COMMISSION
 JUN - 5 1980
 CONSERVATION DIVISION
 Topeka, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the GATES #1, SE NW SW, Section 23-8S-24W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 2nd day of June, 1980.



Sherrie L. Brooks
 Sherrie L. Brooks, Notary Public