

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Rine of Petroleum Management, Inc., has this
date requested permission to plug the following described well:Mr. Rine guarantees payment of the plugging fee.Operator's full Name: Petroleum Management, Incorporated,Complete Address: 1515 KSB&T Building, Wichita, Kansas.Lease Name: Holly Unit Well No. 7-2Location: SE-NE-NE Sec. 31 Twp. 8 Rge. (E)(W) 24County: Graham Total Depth 3888' Oil Well Gas Well Input Well X SWD Well D & A Lost Hole Mr. Rine was instructed to plug the well as follows:240'--8 5/8" Surface casing, cement circulated with 150 Sx.
3383'--5 1/2" Production casing cemented on bottom with 75 Sx. Junk in
hole @ 2607'.When well was opened it flowed salt water, squeezed 5 1/2" with 35 Sx.
cement followed by plug to top of junk @ 2607'. Pull 5 1/2" casing and
squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft. cement,
staged.

Very truly yours,

Conservation Division Agent