



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: 1515 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Holley Unit Well No. Tract #6, Well #5

Location: SE-SW-NW Sec. 31 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 4045' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

318'--10 3/4" Surface casing, cement circulated with 210 Sx. (9" Hole).
4044'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool
set @ 2208 with 150 Bbl Black Magic circulated to surface. Well plugged
back to 400' with top of perforations @ 3976'.

Sand well back to 3950' and set 6 Sx. cement with dump bailer. Pull 7"
casing and squeeze well with 7 sacks hulls, 50 sacks gel and 220 Cu. Ft.
cement, staged.

Very truly yours,

A. L. Nichols
Conservation Division Agent