



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 23 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wayne Fuzzell of Petroleum Management, Inc., has this

date requested permission to plug the following described well:

Mr. Fuzzell guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated.

Complete Address: 1515 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Holley Unit Well No. 6-7

Location: NW-SE-NW Sec. 31 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 4010' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Fuzzell was instructed to plug the well as follows:

328'--10 3/4" Surface casing, cement circulated with 210 Sx.  
4003'--7" OD Production casing cemented on bottom with 100 Sx. Well  
plugged back to 3997' Top perforations from 3940' to 3944'.

Sand well back to 3925' and set 7 Sx. cement with dump bailer. Pull 7"  
casing and squeeze well with 7 sacks hulls, 50 sacks gel and 210 Cu. Ft.  
cement, staged.

Very truly yours,

*W. L. D. Schick*  
Conservation Division Agent