

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

FEB 26 1974

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Don Rine of Petroleum Management, Inc., has this  
date requested permission to plug the following described well:Mr. Rine guarantees payment of the plugging fee.Operator's full Name: Petroleum Management, Incorporated.Complete Address: 1515 KSB&T Building, Wichita, Kansas.Lease Name: Holly Unit Well No. 6-12Location: SE-SE-SW Sec. 31 Twp. 8 Rge. (E)(W) 24County: Graham Total Depth 3978' Oil Well Gas Well  Input Well X SWD Well  D & A  Lost Hole Mr. Rine was instructed to plug the well as follows:318'--10 3/4" Surface casing, cement circulated with 210 Sx.  
3972'--7" OD Production casing cemented on bottom with 100 Sx. Top  
perforations from 3864' to 3878'.Sand well back to 3850' and set 6 Sx. cement with dump bailer. Pull  
7" casing and squeeze well with 7 sacks hulls, 50 sacks gel and 120 Sx.  
Halliburton Lite Cement, staged.

Very truly yours,

  
A. L. Dickels  
 Conservation Division Agent