



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wayne Fuzzell of Petroleum Management, Inc. has this date requested permission to plug the following described well:

Mr. Fuzzell guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated.

Complete Address: 1515 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Holley Unit Well No. 6-11

Location: CS/2-S/2-SW Sec. 31 Twp. 8 Rge. (E)(W) 21

County: Graham Total Depth 3991' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Fuzzell was instructed to plug the well as follows:

312'--10 3/4" Surface casing, cement circulated with 210 Sx.
3986'--7" OD Production casing cemented on bottom with 100 Sx. No plug-
back indicated. Top perforations from 3851 1/2 to 3991'.

Sand well back to 3800' and set 6 Sx. cement with dump bailer. Pull 7"
casing and squeeze well with 7 sacks hulls, 50 sacks gel and 210 Cu. Ft.
cement, staged.

Very truly yours,

H. L. Dehak
Conservation Division Agent