

State of Kansas



15-065-20700-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1974

CONSERVATION DIVISION
Wichita, Kansas

Handwritten signature and date: 9/23/74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: C & G Drilling Company,

Complete Address: 1107 Union National Building, Wichita, Kansas.

Lease Name: Ostmeyer Well No. 1

Location: NW-NW-SE Sec. 15 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3910' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

226'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 875'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Handwritten signature: M. L. Nichols
Conservation Division Agent