

State of Kansas



15-063-30283-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1967
626-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Helberg Oil Company has this date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Helberg Oil Company,

Complete Address: Morland, Kansas.

Lease Name: Marion C. Helberg Well No. 2

Location: SW-SW-SE Sec. 19 Twp. 8 Rge. (E)(W) 25

County Graham Total Depth 1070 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Helberg was instructed to plug the well as follows:

This well was started as an anhydrite test, no surface pipe was set, 7 7/8" hole from bottom of cellar to TD. Hole was lost due to pipe slip having been dropped in hole.

Push plug to 500' and displace 20 Sx. cement thru drill pipe.

Heavy mud to 150', set bridging plug with 1/2 sack hulls and fill hole to bottom of cellar with 50 Sx. cement.

Very truly yours,

H. S. Nichols
Conservation Division Agent