



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1966

3-28-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sam Bradley of Pipe Pullers, Inc., has this

date requested permission to plug the following described well:

McAdams Pipe & Supply

Mr. Bradley guarantees payment of the plugging fee.

Operator's full Name: McAdams Pipe and Supply Company,

Complete Address: Box # 295, Great Bend, Kansas.

Lease Name: A. Schmeid Well No. 1

Location: CNE-NE Sec. 20 Twp. 8 Rge. (E)(W) 25

County Graham Total Depth 3886 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bbadley was instructed to plug the well as follows:

204'--8 5/8" Surface pipe, cement circulated with 125 Sx.
3884'--5 1/2" Production casing cemented with 125 Sx. Well
plugged back to 3853. Top perforations from 3828' to 3836'.

Sand well back to 3815 and set 5 Sx. cement with dump bailer.
pull 5 1/2" to 600' and circulate heavy gel mud, pull 5 1/2" to
540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 195'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock
bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

N. L. Nichols
Conservation Division Agent