

State of Kansas



15-065-01348-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 8 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 11/8/68

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Herman Fellhoelter of Ivy Oil Company, has this date requested permission to plug the following described well:

Mr. Fellhoelter guarantees payment of the plugging fee.

Operator's full Name: Ivy Oil Company,

Complete Address: Box #86, Plainville, Kansas.

Lease Name: Adelia Schmeid Well No. 1-C

Location: NE-NE-NW Sec. 21 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3856 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Fellhoelter was instructed to plug the well as follows:

199'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3855'--4 1/2" Production casing cemented on bottom with 125 Sx. Plugged back to 3814. Top perforations @ 3701.

Sand well back to 3650' and set 3 Sx. cement with dump bailer. Pull 4 1/2", and squeeze well with heavy drilling mud and 130 Sx. cement staged.

Very truly yours,

*M. G. Nichols*

Conservation Division Agent