

State of Kansas



15-065-01349-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 8 1968
 CONSERVATION DIVISION
 Wichita, Kansas

11/8/68

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Herman Fellhoelter of Ivy Oil Company, has this date requested permission to plug the following described well:

Mr. Fellhoelter guarantees payment of the plugging fee.

Operator's full Name: Ivy Oil Company,

Complete Address: Box #86, Plainville, Kansas.

Lease Name: Adelia Schmeid Well No. 2-C

Location: CN/2-N/2-NW Sec. 21 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3865 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Fellhoelter was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 125 Sx.
3864'--5 1/2" Production casing cemented on bottom with 100 Sx. Well
plugged back to 3828'. Top perforations @ 3766'.

Sand well back to 3750' and set 5 Sx. cement with dump bailer. Pull
5 1/2" casing and squeeze well with heavy drilling mud and 130 Sx. cement
staged.

Very truly yours,

Conservation Division Agent