

State of Kansas



15-065-01350-00-01

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
11/6/68

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Herman Fellhoelter of Ivy Oil Company, has this date requested permission to plug the following described well:

Mr. Fellhoelter guarantees payment of the plugging fee.

Operator's full Name: Ivy Oil Company,

Complete Address: Box #86, Plainville, Kansas.

Lease Name: Adelia Schmeid Well No. 3-C

Location: NW-NW-NW Sec. 21 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3880' Oil Well

Gas Well      Input Well X SWD Well      D & A      Lost Hole     

Mr. Fellhoelter was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 115 Sx.  
3876'--5 1/2" casing cemented on bottom with 125 Sx. Well plugged back to 3850'.  
Top perforations @ 3718'.

Push plug to 3600', build sand bridge and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" casing and squeeze well with heavy rotary drilling mud and 130 Sx.  
cement staged.

Very truly yours,

Conservation Division Agent