

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Vincent Oil Corporation  
Address: 155 N. Market, Suite 700  
Phone: (316) 262-3573 Operator License #: 5004  
Type of Well: D&A Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 3-26-2008 (Date)  
by: Lin Reimer, KCC District I, Dodge City, Ks (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 4736  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 097-21633-0000  
Lease Name: Mull  
Well Number: 6-1  
Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - NW - SE  
1980 Feet from  North /  South Section Line  
1980 Feet from  East /  West Section Line  
Sec. 1 Twp. 27 S. R. 17  East  West  
County: Kiowa  
Date Well Completed: 3-29-2008  
Plugging Commenced: 3-29-2008  
Plugging Completed: 3-29-2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	417'	8 5/8"	417'	0'

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 18 2008  
CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole filled with drilling mud, spotted cement plugs through drill pipe at following depths: 50 sx plug at 1170', 50 sx plug at 450', and a 20 sx plug at 60' to surface. Plugged rotary mouse hole with 10 sx cement and rotary rat hole with 15 sx cement. Cement used in plugging operations was 60 / 40 Poz with 4% gel.

*KCCPKT*

Name of Plugging Contractor: Pickrell Drilling Company Inc. License #: 5123  
Address: 100 S. Main, Suite 505, Wichita, Kansas 67202


Name of Party Responsible for Plugging Fees: Vincent Oil Corporation, (155 N. Market, Suite 700, Wichita, Kansas 67202)  
State of Kansas County, Sedgwick, ss.

M.L. Korpage (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *M.L. Korpage*  
(Address) 155 N. Market, Suite 700, Wichita, Kansas 67202

SUBSCRIBED and SWORN TO before me this 16th day of April

*Yolanda Eubanks* My Commission Expires:  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*PK*

# ALLIED CEMENTING CO., LLC. 31061

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
*Medicine Lodge, KS.*

DATE <i>3-29-08</i>	SEC. <i>1</i>	TWP. <i>27S</i>	RANGE <i>17W</i>	CALLED OUT <i>9:30 AM</i>	ON LOCATION <i>12:00 PM</i>	JOB START <i>7:00 PM</i>	JOB FINISH <i>9:30 PM</i>
LEASE <i>Mull</i>		WELL# <i>G-1</i>		LOCATION <i>Haviland, KS, 7N, 1W, 10N, 12W</i>		COUNTY <i>Kiowa</i>	STATE <i>KS</i>
OLD OR NEW (Circle one) <u>NEW</u>				To Gate, N INTO			

CONTRACTOR *Pickrell*

TYPE OF JOB *Rotary Plug*

HOLE SIZE *7 7/8* T.D.

CASING SIZE *8 7/8* DEPTH *418'*

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX *500* MINIMUM *100*

MEAS. LINE SHOE JOINT *—*

CEMENT LEFT IN CSG. *See Remarks*

PERFS.

DISPLACEMENT *See Remarks*

OWNER *Vincent oil corp*

CEMENT AMOUNT ORDERED *1455x 60:40:4'*

COMMON	<i>87 A</i>	@	<i>14.20</i>	<i>1235.40</i>
POZMIX	<i>58</i>	@	<i>7.20</i>	<i>417.60</i>
GEL	<i>5</i>	@	<i>18.75</i>	<i>93.75</i>
CHLORIDE		@		
ASC		@		
HANDLING	<i>150</i>	@	<i>2.15</i>	<i>322.50</i>
MILEAGE	<i>30 x 150</i>	x	<i>0.09</i>	<i>405.00</i>
TOTAL				<i>2474.25</i>

RECEIVED  
KANSAS CORPORATION COMMISSION  
**APR 18 2008**  
CONSERVATION DIVISION  
WICHITA, KS

EQUIPMENT

PUMP TRUCK # *414* CEMENTER *Thomas Denorow*  
HELPER *Greg Co*

BULK TRUCK # *364* DRIVER *Michael N.*

BULK TRUCK # DRIVER

**REMARKS:**

*Pipe set @ 1170' Load Hole, Pump 50sf 60:40:4  
Displace w/ 13 1/4 Bbl mud hater, Pipe set @  
450' Load Hole, Pump 50sf 60:40:4, Displace w/  
3 1/4 Bbl Fresh, Pipe set @ 60' Pump 20sf  
60:40:4 cement circulated to surface, Plug  
at w/ 15 sf 60:40:4 + mouse w/ 10sf 60:40:4*

*Thank you*

CHARGE TO: *Vincent oil corp*

STREET

CITY STATE ZIP

**SERVICE**

DEPTH OF JOB	<i>1170'</i>		
PUMP TRUCK CHARGE			<i>917.00</i>
EXTRA FOOTAGE		@	
MILEAGE	<i>30</i>	@	<i>7.00</i>
MANIFOLD		@	
TOTAL <i>1127.00</i>			

**PLUG & FLOAT EQUIPMENT**

	@		
<i>NONE</i>	@		
	@		
	@		
TOTAL			

To Allied Cementing Co., LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME *Shane Downs*

SIGNATURE *Shane Downs*

SALES TAX (If Any)

TOTAL CHARGES *2474.25*

DISCOUNT *2474.25* IF PAID IN 30 DAYS

**ANY APPLICABLE TAX  
WILL BE CHARGED  
UPON INVOICING**