

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: KNIGHTON OIL COMPANY, INC.  
Address: 1700 N. Waterfront Parkway, Suite 100, Bldg. A  
Phone: (316) 630-9905 Operator License #: 5010  
Type of Well: Oil Well Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 4/7/08 (Date)  
by: Richard Williams (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3640 Bottom: 3642 T.D. 3642  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-051-19198-00-00  
Lease Name: Solomon  
Well Number: 8  
Spot Location (QQQQ): C - SW - NE - NW  
4290 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 33 Twp. 11 S. R. 19  East  West  
County: Ellis  
Date Well Completed: 1/22/1953  
Plugging Commenced: 4/07/2008  
Plugging Completed: 4/07/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil	Surface	108'	8 5/8"	108'	none
		Surface	3640'	4 1/2"	3640'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

First plug at 1780' with 100 sacks cement, 60/40, 4% gel, second plug at 900' with 150# hulls and 50 sacks cement, cement did circulate.  
8 5/8" casing, 40 sacks cement with 200 p.s.i. and 4 1/2" casing 50 # hulls and 160 sacks, top off.  
Used a total of 350 sacks cement, 60/40, 4% gel and 200# hulls.

Name of Plugging Contractor: Express Well Service License #: 6426 RECEIVED  
Address: P.O. Box 19 Victoria, KS 67671 KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Knighton Oil Company, Inc. APR 18 2008  
State of Kansas County, Sedgwick, ss. CONSERVATION DIVISION  
WICHITA, KS

Earl M. Knighton, Jr (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Earl M. Knighton Jr.  
(Address) 1700 N. Waterfront Parkway, Suite 100, Bldg. A

**DAVID D. MONTAGUE**  
Notary Public - State of Kansas  
My Appt. Expires 10-4-11

SUBSCRIBED and SWORN TO before me this 16th day of April, 20 08  
[Signature] My Commission Expires: 10-4-11  
Notary Public

PKT