

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: PO Box 2528 Liberal KS 67905
Phone: 620 629 4200 Operator License #: 5447
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3-10-08 (Date)
by: Lin Reimer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow/Keyes Depth to Top: 4783 Bottom: 4836 T.D. 4900

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-20764-00-00
Lease Name: Miller Q
Well Number: 2 KCC PRT P21 CP213
Spot Location (QQQQ): E2-NE-NW-SW
2310 Feet from North / South Section Line
1250 Feet from East / West Section Line
Sec. 29 Twp. 33 S. R. 42 East West
County: Morton
Date Well Completed: 7-25-85 spud
Plugging Commenced: 3-11-08
Plugging Completed: 3-12-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1368	—
				5 1/2	4899	1536

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

HLS set CIBP + 2sx in 5 1/2 from 4650 to 4630 (Pumped mud before CIBP). Shot & pulled 5 1/2 to 1400. Circ. hole w/mud & mixed 50 sx plug 1400 to 1250 40 sx 600 to 480 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS, 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) Kenny Andrews
(Address) PO Box 2528 Liberal, KS, 67905

SUBSCRIBED and SWORN TO before me this 21 day of April, 2008
Anita Peterson My Commission Expires: Oct. 1, 2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

APR 25 2008

CONSERVATION DIVISION
WICHITA, KS

ANITA PETERSON
Notary Public - State of Kansas
My Appt. Expires October 1, 2009