


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham

County. Sec. 28 Twp. 8S Rge. 24W (E) (W)

Location as "NE/CNWxSWx" or footage from lines. SE SE NW
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Findley "A" Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 8, 19 56
Application for plugging filed June 26, 19 56
Application for plugging approved June 26, 19 56
Plugging commenced June 28, 19 56
Plugging completed June 28, 19 56
Reason for abandonment of well or producing formation No oil

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3872 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	6-8-56	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock to 3650',
dumped 4 sacks cement at 3650' with
dump bailer. Top of cement, 3620'. Filled
hole with mud to 200', set rock bridge,
dumped 15 sacks cement. Top of cement, 160'.
Filled hole with mud to 35', set rock bridge,
dumped 10 sacks cement for cap.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Miller Casing Pulling Company
Address P. O. Box 711, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: *Raymond L. Bacon* V-P
903 Union National Bank Bldg. Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of July, 19 56

My commission expires April 18, 1959 RECEIVED Frances E. Barnham Notary Public.



AUG 2 1956
8-2-1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 28 T 8 R 24W
BOOK PAGE 74 LINE 37

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
903 Union National Bank Building
Wichita 2, Kansas

Findley A No. 2
SE SE NW Sec. 28-8S-24W
Graham County, Kansas

Total Depth: 3872'

Elevation: 2311' R.B.

Commenced: 5-26-56 Completed: 6-8-56 Production: D & A

Contractor: Harms-Burt Drilling Company
Great Bend, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 193' with 175 sacks cement.

Figures indicate bottom of formations:

Shale	820'		
Shale & Sand	1560'		
Sand	1710'		<u>TOPS</u>
Shale & Red Bed	1930'	Heebner	3609' (-1298)
Shale	2000'	Lansing	3647' (-1336)
Anhydrite	2035'	Total Depth	3872' (-1561)
Shale & Shells	2755'		
Lime	2845'		
Lime & Shale	3640'		
Lime	3872'		
Total Depth	3872'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

PLUGGING
FILE SEC. 28 T. 8 R. 24W
BOOK PAGE 74 LINE 37

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. Bacon
Vice-President

Subscribed and sworn to before me this 26th day of June, 1956.

My Commission Expires:

April 18, 1959

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
JUN 27 1956
6-27-1956

Frances E. Barber
Notary Public

