

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 28 Twp. 8S Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW SW

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Findley "B" Well No. 5

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 8, 19 56

Application for plugging filed October 8, 19 56

Application for plugging approved October 8, 19 56

Plugging commenced October 8, 19 56

Plugging completed October 8, 19 56

Reason for abandonment of well or producing formation No oil in commercial quantities found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3912 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	10-8-56	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with heavy mud to 190',
set No. 1 plug with 15 sacks cement.
Set No. 2 plug at 35' with heavy mud
and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1956
10-18-1956
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address 903 Union National Bldg., Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

By: Raymond L. Bacon V-P
903 Union National Bldg., Wichita, Kansas
(Address)

17th day of October, 19 56

Frances E. Barham
Notary Public.



PLUGGING
FILE SEC 28 T. 8. R24W
BOOK PAGE 107 L1E, 21

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
903 Union National Bldg.
Wichita, Kansas

Findley "B" No. 5
NE SW SW Sec. 28-8S-24W
Graham County, Kansas

Total Depth: 3912'

Elevation: 2358' R.B.
Production: D & A

Commenced: 9-29-56 Completed: 10-8-56

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface pipe at 197' with 150 sacks cement.

Figures indicate bottom of formations:

Rock & Clay	25'		
Shale & Shells	197'		
Shale	760'		
Sand & Shale	1340'	Anhydrite	2047' (✓ 311)
Shale	1610'	Heebner	3660' (-1302)
Sand	1790'	Lansing	3699' (-1341)
Shale	1800'	Rotary Total Depth	3912' (-1554)
Shale, Sand & Red Bed	2047'		
Anhydrite	2075'		
Shale & Red Bed	2360'		
Shale & Lime	3130'		
Lime	3335'		
Lime & Shale	3708'		
Lime	3912'		
Total Depth	3912'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

MINERAL COMMISSION

IMPERIAL OIL OF KANSAS, INC.

OCT 18 1956
10-18-1956
CONSERVATION DIVISION
Wichita, Kansas

By: Ray L. H. [Signature]
Vice-President

Subscribed and sworn to before me this 17th day of October, 1956.

My Commission Expires:
April 18, 1959

PLUGGING
FILE SEC 28 T 8 R24W
BOOK PAGE 107 LINE 31

Francis E. [Signature]
Notary Public

