

15-065-00864-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 29 Twp. 8 Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines. SW NE SE

Lease Owner El Dorado Refining Company

Lease Name Keith Well No. 2

Office Address 306 Koch Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 5 19 56

Application for plugging filed February 5 19 56

Application for plugging approved February 5 19 56

Plugging commenced February 5 19 56


Plugging completed February 5 19 56

Reason for abandonment of well or producing formation no oil in commercial quantities found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3945 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	304	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 290'. Set #1 Plug with 1/2 sack Hulls and 15 sacks cement. Filled hole with extra heavy rotary mud to 40'. Set #2 plug with 1/2 sack Hulls and 10 sacks cement.

RECEIVED
COMMISSION
2-9-1956

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 1005 Central Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss. R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.R. McNicol
R. R. McNicol
1005 Central Building, Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 8th day of February, 19 56

My commission expires September 30, 1959

Darlene May
Notary Public.



PLUGGING
FILE SEC 29 T 8 R 24W
BOOK PAGE 37 LINE 5

ROTARY DRILLING LOG

OPERATOR: El Dorado Refining Company
 Keith #2
 SW NE SE Sec. 29-8-24W,
 Graham County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 1/22/56
 COMP: 2/5/56

Formations:

Post Rock & Clay	560'
Shale & Shells	304'
Shale	725'
Shale & Shell	1175'
Sand & Shale	1380'
Shale & Shell	1890'
Shale & Red bed	2095'
Anhydrite	2135'
Shale	2140'
Shale & Shell	2350'
Shale & Lime	2390'
Shale & Shells	2675'
Shale & Chert	2695'
Shale & Lime	2800'
Shale Lime Strks.	2930'
Lime & Shale	3125'
Shale Lime Streaks	3250'
Shale & Lime	3660'
Lime	3945'
Rotary Total Depth (D&A)	3945'

Remarks: Set 8-5/8" casing at 304'
 cemented with 225 sacks pozmix, 2%
 C. C.

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol

STATE OF KANSAS
 FEB 9 1956
 COMM. 2-9-1956
 VICTOR R. ROSS

PLUGGING
 FILE SEC. 29 T 8 R 24W
 BOOK PAGE 37 LINE 5