


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 29 Twp. 8S Rge. 24 (E) (XX)  
Location as "NE/CNW/SW" or footage from lines. NE SE NE  
Lease Owner Cities Service Oil Company  
Lease Name Holley North Well No. 302W  
Office Address 209 E. William, 700 Sutton Place Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Inj.  
Date well completed 11-16 1964  
Application for plugging filed 8-10 1973  
Application for plugging approved 8-13 1973  
Plugging commenced 2-11 1974  
Plugging completed 2-12 1974  
Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production ----- 19-----  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation Lansing Kansas City Depth to top ----- Bottom ----- Total Depth of Well 3900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	195'	None
				5 1/2"	3900'	827'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

Pumped 5 sacks hulls, 13 sacks gel, 70 sacks cement (1125' to 800'), 15 sacks gel (800' to 200'), 20 sacks cement (200' to 125'), 2 sacks gel (125' to 45'), 10 sacks cement (45' to surface). Maximum pressure 300, minimum 200, SIP 100 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 27 1974  
2-27-1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Haliburton Services  
Address P. O. Drawer 1431, Duncan, Oklahoma 73533

STATE OF Kansas COUNTY OF Sedgwick, ss.  
E. W. Peterman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

DEAN CALDWELL  
State Notary Public  
Sedgwick County, Kansas  
Comm. Expires Oct 16, 1978

(Signature) *E. W. Peterman*  
209 E. William, 700 Sutton Pl. Bldg. Wichita, KS  
(Address) 67202

to before me this 22nd day of February, 1974

*Dean Caldwell*  
Notary Public.

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
903 Union National Bank Bldg.  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 13 1973  
8-13-1973  
CONSERVATION DIVISION  
Wichita, Kansas

Graham No. 2  
NE SE NE Sec. 29-8S-24W  
Graham County, Kansas

Total Depth: 3900'

Elevation: 2382' R.B.

Commenced: 5-5-56 Completed: 5-15-56 Production: 360 Bopd, No water

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 195' with 175 sacks cement.

Figures indicate bottom of formations:

Sand and Clay	50'		
Shale	1055'		
Sand and Shale	1310'		
Shale	1645'	Heebner	<u>TOPS</u> 3670' (-1288)
Sand	1835'	Lansing	3709' (-1327)
Shale and Red Bed	2080'	Total Depth	3900' (-1518)
Anhydrite	2115'		
Shale and Red Bed	2345'		
Shale	2460'		
Lime and Shale	2685'		
Lime	2870'		
Lime and Shale	3550'		
Lime	3900'		
Total Depth	3900'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. Brown  
Vice-President

Subscribed and sworn to before me this 4th day of June, 1956.

My Commission Expires:

April 18, 1959

Frances E. Barham  
Notary Public