


15-065-02041-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas



Locate well correctly on above Section Plat

Graham County. Sec. 1 Twp. 8S Rge. 24W (X) (W)  
Location as "NE/CNW/SW" or footage from lines NW 1/4 SE 1/4 NE 1/4  
Lease Owner Leben Drilling, Inc. & Houston, Chandler & Simpson  
Lease Name Hutton Well No. 2  
Office Address 905 Central Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-6-59 19  
Application for plugging filed 3-6-59 19  
Application for plugging approved 3-6-59 19  
Plugging commenced 3-6-59 19  
Plugging completed 3-6-59 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3822 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	212	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
1st plug @ 600' with 20 sacks cement.  
2nd plug @ 215' with 20 sacks cement.  
Top plug @ 40' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 21 1959

CONSERVATION DIVISION  
Wichita, Kansas

3/27/59

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
I, Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin  
905 Central Bldg., Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 19 59  
My commission expires June 17, 1961  
Ruth N. Benjamin Notary Public.

PLUGGING  
FILE SEC. 1 T 8 R 24w  
BOOK PAGE 17 LINE 3

15-065-02041-00-00

RECEIVED  
STATE CORPORATION COMMISSION

2/21/59

MAR 21 1959

DRILLER'S LOG

CONSERVATION DIVISION  
Wichita, Kansas

COMPANY: **LEBEN DRILLING, INC. & HOUSTON, CHANDLER & SIMPSON OIL CO.**

CONTRACTOR: **LEBEN DRILLING, INC.**

FARM: **HUTTON #2**

LOCATION: **NW 1/4 SE 1/4 NE 1/4 SEC. 1-8S-24W, GRAHAM COUNTY, KANSAS**

COMMENCED: **JANUARY 28, 1959**

COMPLETED: **FEBRUARY 5, 1959**

0	40	Clay	TOPS:	
40	220	Shale & Sand	Topoka	3242
220	1110	Shale, Shell & Sand	Heabner	3571
1110	1575	Shale & Sand	Toronto	3594
1575	1790	Sand	Lansing-KC	3610
1790	1820	Redbed & Sand	Base K.C.	3818
1820	2290	Shale & Redbed	Elevation	2341 RB
2290	2430	Shale & Shells		
2430	3625	Lime & Shale		
3625	3720	Lime		
3720	3775	Lime & Shale		
3775	3818	Lime		
3818	3822	Shale		
	3822	Rotary Total Depth - D & A		

Set 8 5/8" surface casing @ 220' with 150 sacks Sunset cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Hutton #2, located NW 1/4 SE 1/4 NE 1/4 of Section 1, Township 8 South, Range 24 West, Graham County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

*Frank Hamlin*  
Frank Hamlin

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) ss:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 10th day of March, 1959

*Ruth H. Benjamin*  
Ruth H. Benjamin, Notary Public

My Commission Expires:  
June 17, 1961



PLUGGING  
FILE SEC. 1 T. 8 R. 24W  
BOOK PAGE 17 LINE 3