

15-065-21630-08-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Graham SEC. 1 TWP. 8s RGE. 24w E/W  
Location as in quarters or footage from lines:  
NE SE SE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Energy Three, Inc.  
Lease Name Gates #1 Well No. \_\_\_\_\_  
Office Address P.O. Box 1505, Great Bend, Ks. 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 1/3/83  
Plugging completed 1/13/83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3880'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	264'	none
				4 1/2"	3879'	2197'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged bottom with sand to 3642' & ran 4 sacks cement, Shot well at 3014', 2527', & 2217'. Pulled total of 53 joints. Plugged well with 2 sacks hulls mixed with 29 gel, 100 sacks cement, 10 gel, 8 5/8 plug, & 70 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 19 83



Irene Hoover  
Notary Public.

My Commission expires:

RECEIVED  
STATE CORPORATION COMMISSION

JAN 20 1983

CONSERVATION DIVISION  
Wichita, Kansas

15-065-21630-00-00

LIG THREE DRILLING INC.

BOX 811  
Russell, Kansas 67665

913-483-5644

RECEIVED  
STATE CORPORATION COMMISSION

OCT 15 1982

CONSERVATION DIVISION  
Wichita, Kansas

10/15/82

Company	Energy Three Inc.
Farm	Gates #1
Location	NE SE SE 1-8-24W
County	Graham
Contractor	Big Three Drilling Inc.
Comm	May 5, 1982
Comm1	May 14, 1983
Total Depth	R.T.D. 3880'
Casing	4 1/2" new
Production	Set pipe

Figure Indicate bottom of formation

Sand & Shale	1910'
Anhy	2000' to 2035'
Lime & Shale	3880'

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

Big Three Drilling Inc.

*Timothy F. Scheck*

Timothy F. Scheck